


STANDARD NOTES:

1. PROVIDE IMPERVIOUS TRENCH DAMS AT A MAXIMUM INTERVAL OF EVERY 300 FT OR A MINIMUM OF ONE DAM BETWEEN MANHOLES.
2. REFER TO TOWN OF CANTON SANITARY SEWER STANDARD DETAILS FOR TRENCHES FOR REMAINING BACKFILL REQUIREMENTS BEYOND THE IMPERVIOUS MATERIAL.
3. REFER TO SECTIONS 02315 AND 02320 FOR ADDITIONAL REQUIREMENTS ASSOCIATED WITH TRENCH DAMS DURING PIPE INSTALLATIONS.
4. IMPERVIOUS MATERIALS SHALL HAVE A COEFFICIENT OF PERMEABILITY NOT TO EXCEED 1×10^{-5} CM/SEC.

**Water Pollution Control Authority
Town of Canton**



4 Market Street
P.O. Box 168
Collinsville, Connecticut 06022

SEWER CONSTRUCTION DETAIL

**IMPERVIOUS TRENCH
INTERRUPTERS / DAMS**

NO SCALE

LATEST REVISION: 2/07 NO. 019